SINKGRAB · DESIGN DECISION RECORD

SinkGrab concept selection, proposed, awaiting Amish

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	SKG-DDR-005	Version	0.1
Status	Draft	Date	2026-10-24
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/sinkgrab		
Source	docs/decisions/0005-concept-selection.md @ ec186d3		

REVISION HISTORY

Version	Date	Author	Change
0.1	2026-10-24	Amish Chadha	First issue (kit 1.9.1 upgrade): concept options A and B scored within 10 %, so both are put to Amish without a pick (STANDARDS section 21)

0005: Concept selection (proposed, awaiting Amish)

- **Date:** 2026-10-24
- **Status:** proposed, awaiting Amish

Context

Kit 1.8 asks every design for at least two concept options with different working principles, scored against the same user requirements (STANDARDS section 21). SinkGrab was designed before kit 1.8, so its current design, the rope grab and under-curb scraper, is option A and is not redesigned without Amish's go. Option B, a dart-valve bailer spudded on a jerk line, was developed in this session and modelled to the same detail level (D3) so the two can be compared on the same footing. The comparison is SKG-OPT-001.

Options considered

Option	Working principle	Weighted score	Strengths	Weaknesses
A, rope grab and under-curb scraper	A one-line clamshell grab digs the flooded rings; a pole scraper cuts under the cutting edge so the lining sinks	167	Undercuts, steers the lining, digs cohesive soils; drawn, priced and planned	More parts and pins; plate rolls for the shells; sinking still at risk (STEM S21)
B, dart-valve bailer on a jerk line	A valved tube is spudded into loose sand by jerking the capstan line sideways; sand runs in from under the edge	153	Simple pipe-and-plate build; about USD 330 cheaper and about 40 kg lighter as modelled; no linkage under water	Sand and gravel only; no undercut or tilt control beyond saddles; heavier jerk effort; shock on the line

The scores are 8.4 % apart, inside the 10 % band, so both go to Amish without a pick.

Decision

None yet. Amish chooses between:

- **A:** keep the rope grab and under-curb scraper as SinkGrab's concept (no change to the repo), optionally carrying a bailer on the same line as an accessory for clean running sand (the runner-up's best idea).
- **B:** move to the dart-valve bailer, accepting that SinkGrab then serves sand and gravel wells only; the drawings, BOM and build plan would be redone for B.

Until Amish decides, `project.yaml` leaves `concept_chosen` unset and the drawings, BOM and build plan stay on option A, which `cad/src/model.py` names as `CHOSEN` because it is the design of record.

Consequences

- If A: no change to the design; UR-011 (soils) and UR-003 (tilt) stay covered. The bailer accessory, if wanted, is a new BOM line and a short build plan section.

- If B: PR-001, PR-003, PR-006 and PR-013 would need restating for sand-only wells; the grab, scraper and two sheaves leave the BOM; a new build plan and drawings follow, and the STEM rows OB3, OB5 and OB6 need test-pit evidence.
- Either way the capstan, foot cradle, drawbar, well-head frame, saddles and safety stops are unchanged.